

## **Technical Details**

Supporting Test Data: 415515 - UL-EU-01023-CRP

Test Standard: EN 1366-3

**Fire Resistance Performance:** 

220mm x 90mm, 2mm Wall Thickness PVC Duct	EI 60 U

U/C, C/C

Supporting Construction:

Flexible walls > 100 mm, Insulated openings , Lined / Unlined

\*The supporting construction must meet the fire resistance requirement of the proposed firestopping detail. Supporting construction must be installed and apertures formed in line with manufacturer's guidance

Service Supports:

< 400mm

Capping

U/C,C/C

\*Service supports must be appropriately fire resistant

Installation:

FSi Ltd. recommend installation of FSi Ltd. products is carried out by 3rd party certified installers.

The substrate must be clean, dry, sound and homogeneous, free from oils, grease, dust and loose particles.

For larger openings, the aperture will need to be filled with Stopseal<sup>®</sup> Batt at the same time as Pipebloc<sup>®</sup> EL is installed. See TDS001 for installation and UL-EU-01023-CPR for tested systems.

For smaller openings / annular space apply Pyrocoustic<sup>®</sup> Sealant at 5mm depth after wrap is installed. Use pointing tool to smooth off

Peel of self adhesive strip. Start to wrap Pipebloc<sup>®</sup> EL 3x Layers to each face of the substrate around the service ensuring enough layers in line with scope of test data, use self-adhesive to secure. Push into aperture or in line with aperture.

Apply the second Pipebloc<sup>®</sup> EL to the other side of the wall. Floor systems require Pipebloc<sup>®</sup> EL from both sides of floor and can be fitted centrally but ensure correct layers are applied as the two systems differ in layers. Pipebloc<sup>®</sup> EL Wraps to be installed to the 3 accessible sides of the service, not required where the soffit meets the PVC Duct.

Minimum Separation Between Penetration Services: - 100mm

Issue No. Drawing Reference Date EL-016 21/11/2024 02

Drawing Title:

TESTED DETAIL

Pipebloc<sup>®</sup> EL System Installed to a PVC Duct in a Flexible Wall to Head of Wall

Scale : NTS

Drawn by : FSi Limited



FSi Promat Limited Westminster Industrial Estate Tamworth Road Measham Leicestershire DE12 7DS